



# TerraFlow® Mill Test Report

Month of Issue: JANUARY 2021

Plant: Seattle, Washington  
Product: TerraFlow 75  
Manufactured: DECEMBER 2020  
Mill Test Report Number: TerraFlow75\_JANUARY2021

## ASTM C 1157 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Slag, %	---	75	Passing 325 Sieve (%)	---	96.3
Type II, %	---	25	Autoclave expansion (%)	0.8	-0.02
			Compressive strength (MPa)		
			3 days	5.0 min	18
			7 days	11.0 min	29
			28 days	--	42

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of applicable Specifications for Type MH

Seattle Plant  
5400 W. Marginal Way SW, Seattle, WA 98106  
Phone: 206-937-8025

Certified By:

Daniel Waldron - QC Laboratory Supervisor

January 14, 2021