

ENX Inc.
Acheson Terminal
10798 HWY 60
Acheson, AB T7X 6N5

Report Date: March 3, 2021
Project Number: 19-01608-002
Test No.: 21ENX-03
Revision: 0

Attention: Mr. Paul Johnson

Test Report Number:	ENX G3-03-21_F_CSA
Year:	2021
Month of Analysis:	March

FLY ASH SOURCE: Genesee Generating Station (G3) SAMPLED BY: Client
SAMPLE DATE: February 15, 2021 SAMPLES RECEIVED: February 23, 2021

CHEMICAL ANALYSIS					
TEST DESCRIPTION	TEST RESULTS	UNITS	SPECIFICATION LIMITS		
			TYPE F	TYPE CI	TYPE CH
Silicon Dioxide (SiO ₂)	59.2	%	-	-	-
Aluminum Oxide (Al ₂ O ₃)	27.7	%	-	-	-
Iron Oxide (Fe ₂ O ₃)	4.5	%	-	-	-
Total (SiO ₂) + (Al ₂ O ₃) + (Fe ₂ O ₃)	91.4	%	-	-	-
Sulphur Trioxide (SO ₃)	0.14	%	5.0% (max)	5.0% (max)	5.0% (max)
Calcium Oxide (CaO)	7.2	%	≤ 15%	> 15% - ≤ 20%	> 20%
Magnesium Oxide (MgO)	1.50	%	-	-	-
Moisture Content ⁽¹⁾	0.39	%	3.0% (max)	3.0% (max)	3.0% (max)
Loss on Ignition (LOI)	1.18	%	8.0% (max)	6.0% (max)	6.0% (max)
Total Equivalent Alkali Content (Na ₂ O _{eq})	3.74	%	-	-	-
Total Available Equivalent Alkali Content (Na ₂ O _{eq})	-	%	-	-	-

(1) Optional requirement as per CSA A3001-18 - Table A.3

PHYSICAL ANALYSIS					
TEST DESCRIPTION	TEST RESULTS	UNITS	SPECIFICATION LIMITS		
			TYPE F	TYPE CI	TYPE CH
Fineness Retained on 45µm (No. 325 Sieve)	27.9	%	34% (max)	34% (max)	34% (max)
Quantity of Air Entrainment	1.0	%	-	-	-
Drying Shrinkage (Increase at 28-days)	0.01	%	-	-	-
Strength Activity Index with Portland Cement ⁽²⁾					
% of Control at 7-Days	78	%	-	-	-
% of Control at 28-Days (previous month's result)	82	%	75% (min)	75% (min)	75% (min)
Water Requirement, Percent of Control	98	%	-	-	-
Soundness, Autoclave Expansion	0.10	%	0.8% (max)	0.8% (max)	0.8% (max)
Density	2.07	g/cm ³	-	-	-

(2) Optional requirement as per CSA A3001-18 - Table A.3

COMMENTS
We hereby certify that the fly ash represented by the above chemical and physical analyses meets the requirements of CSA A3001-18 for Type F. Testing performed by accredited laboratory in accordance with CSA A283-19 and Canadian Council of Independent Laboratories (CCIL) certification requirements.

Report prepared by:

EXL Engineering Inc.



Gene Lecuyer, P. Eng.
Senior Materials Engineer



Results pertain only to the sample(s) provided and constitutes a testing service only. Engineering interpretation or evaluation of the test results will be provided upon written request only.