



TerraFlow® Mill Test Report

Month of Issue: APRIL 2021

Plant: Seattle, Washington
Product: TerraFlow 75
Manufactured: MARCH 2021
Mill Test Report Number: TerraFlow75_APRIL 2021

ASTM C 1157 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Slag, %	---	75	Passing 325 Sieve (%)	---	95.2
Type IL, %	---	25	Autoclave expansion (%)	0.8	-0.03
			Compressive strength (MPa)		
			3 days	5.0 min	16.3
			7 days	11.0 min	25.1
			28 days	--	34.6

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of applicable Specifications for Type MH

Seattle Plant
5400 W. Marginal Way SW, Seattle, WA 98106
Phone: 206-937-8025

Certified By:

Daniel Waldron - QC Laboratory Supervisor

April 14, 2021