



TerraFlow® Mill Test Report

Month of Issue: OCTOBER 2021

Plant: Seattle, Washington
Product: TerraFlow 75
Manufactured: SEPTEMBER 2021
Mill Test Report Number: TerraFlow75_OCTOBER 2021

ASTM C 1157 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Slag, %	---	75	Passing 325 Sieve (%)	---	94.9
Type IL, %	---	25	Autoclave expansion (%)	0.8	-0.07
			Compressive strength (MPa)		
			3 days	5.0 min	10.7
			7 days	11.0 min	19.9
			28 days	--	30.4

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of applicable Specifications for Type MH

Seattle Plant
5400 W. Marginal Way SW, Seattle, WA 98106
Phone: 206-937-8025

Certified By:

Daniel Waldron - QC Laboratory Supervisor

October 15, 2021