



TerraFlow® Mill Test Report

Month of Issue: JULY 2022

Plant:	Seattle, Washington
Product:	TerraFlow 90
Manufactured:	JUNE 2022
Mill Test Report Number:	TerraFlow90_JULY2022

ASTM C 1157 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Slag, %	---	90	Passing 325 Sieve (%)	---	94.3
			Autoclave expansion (%)	0.8	-0.04
			Compressive strength (MPa)		
			3 days	5.0 min	15.1
			7 days	11.0 min	22.5
			28 days	--	31.2

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of applicable Specifications for Type MH

Seattle Plant
 5400 W. Marginal Way SW, Seattle, WA 98106
 Phone: 206-937-8025

Certified By:

Daniel Waldron - QC Laboratory Supervisor

July 15, 2021