

Cement Mill Test Report

Date of Issue: August 12, 2022

Plant: Exshaw, AB

Product: Portland Cement Type I/II/V

Mill Test Report Number: MTR-I/II/V-2022-07
Manufactured: July 1-31, 2022

ASTM C 150-21 and AASHTO M 85-18 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Rapid Method, X-Ray (C114)			Air content of mortar (%) (C185)	12 max	5
SiO ₂ (%)		19.7			
Al ₂ O ₃ (%)	6.0 max	4.0	Blaine Fineness (m ² /kg) (C204)	260 min	388
Fe ₂ O ₃ (%)	6.0 max	3.6			
CaO (%)		62.2	Passing 45 μm (%) (C430)		98.6
MgO (%)	6.0 max	4.8			
SO ₃ (%)	2.3 max *	2.9	Autoclave Expansion (%) (C151)	0.80 max	0.11
Loss on Ignition (%)	3.5 max	2.5			
Insoluble Residue (%)**	1.5 max	0.35	Compressive strength (MPa, [psi]) (C 10	09)	
CO ₂ (%)		1.9			
Limestone (%)	5.0 max	4.5	3 days	12.0 [1740] min	28.5 [4130]
CaCO ₃ in Limestone (%)	70 min	87	7 days	19.0 [2760] min	35.4 [5130]
Inorganic Process Addition	5.0 max	-	28 days (Reflects previous month's data)		45.4 [6580]
(Lafarge Cement Kiln Dust)					
			Time of setting (minutes)		
Adjusted Potential Phase Composition (C 50)			Vicat Initial (C191)	45 - 375	120
C₃S (%)		56			
C ₂ S (%)		14			
C ₃ A (%)	5 max	4			
C ₄ AF (%)		11	Sulfate Resistance (%) (C452)**	0.040 max	0.030
$C_4AF + 2(C_3A)$	25 max	19	Mortar Bar Expansion (%) (C1038)	0.020 max	0.011
C ₃ S+4.75*C ₃ A (%)	100 max	75			
ASTM C 150-17 and AASHTO M 85-17 Optional Requirements:					
NaEq (%)	0.60 max	0.55	False set (%) (C451)	50 min	87

^{*} May exceed the SO₃ maximum based on C 1038 results of <0.020% expansion at 14 days.

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of ASTM C 150-21 & AASHTO M 85-18 STANDARD SPECIFICATIONS FOR TYPES I, II & V CEMENTS; and ASTM C 150-21 & AASHTO M 85-18 OPTIONAL CHEMICAL REQUIREMENTS FOR TYPES I, II & V LOW ALKALI CEMENT.

Certified By:

Western Canada BU - Exshaw Plant P.O. Box 160, Highway 1A, Exshaw AB, T0L 2C0

Phone: 403-673-3815

Lorraine Richards

Lorraine Richards Quality Manager

^{**} Current Production run not available - most recent provided



Cement Mill Test Report

Date of Issue: August 12, 2022

Plant: Exshaw AB

Product: Portland Cement Type I/II/V

Mill Test Report Number: MTR-I/II/V-2022-07
Manufactured: July 1-31, 2022

ASTM C 150-21 and AASHTO M 85-18 Standard Requirements

Additional Data

Item	Test Result		
	Limestone	Inorganic Process Addition	
		Lafarge Cement Kiln Dust	
Amount (%)	4.5	-	
SiO ₂ (%)	1.0	n/a	
Al ₂ O ₃ (%)	0.6	n/a	
Fe ₂ O ₃ (%)	0.2	n/a	
CaO (%)	51.2	n/a	
SO ₃ (%)	0.2	n/a	
CO ₂ (%)	42.6	n/a	

Base Cement Phase Composition

Item	Test Result
C ₃ S (%)	58
C ₂ S (%)	15
C ₃ A (%)	4
C ₄ AF (%)	12

We certify that the data above reflects the materials used in cement manufacture during the production period indicated.

Note: Specifc Gravity for Portland Cements is 3.14

Certified By:

Western Canada BU - Exshaw Plant P.O. Box 160, Highway 1A, Exshaw AB, TOL 2C0

Phone: 403-673-3815

Lorraine Richards

Quality Manager