

**Cement**

**NewCem Plus**

Analysis by: Lafarge Concrete Lab  
 Sample from : Seattle Blending Facility  
 Average Analysis: November 2022  
 Mill Certificate ID: 12-22 BSCM



Certified to  
NSF/ANSI/CAN 61

**Chemical Analysis**

Total Alkalies as Equivalent Na <sub>2</sub> O	2.59 %
CaO Fly Ash *	15 %
SO <sub>3</sub> Fly Ash *	1.0 %
SO <sub>3</sub> Slag **	5.4 %
S Ion Slag **	0.8 %

**Physical Analysis**

Ground Granulated Blast Furnace Slag SAI, 28 Day **	110 %
Class/Type F Fly Ash Pozzolanic Activity Index, 28 Day *	106 %
LOI Fly Ash *	0.11 %
Autoclave Fly Ash *	0.02 %
Autoclave Slag **	-0.01 %
45 <sub>u</sub> Fly Ash*	17.0 %
45 <sub>u</sub> Slag**	5.8 %
Density	2.78 Mg/m <sup>3</sup>

**Cementitious Blend**

Class/Type F Fly Ash Blend Percentage	50 %
Ground Granulated Blast Furnace Slag Blend Percentage	50 %

We hereby certify this blended SCM product meets the requirements of ASTM C-1697 SCMb-50S/50F and CSA A-3000 BMB-50F/S.

Certified : 

Rob Shogren, P.E.  
 Technical Engineer  
 Lafarge North America

\* 12-22F Centralia Class/Type F Fly Ash Cert

\*\* SEA\_NEWCEM\_Dec22 Ground Granulated Blast Furnace Slag Cert