



# TerraFlow® Mill Test Report

Month of Issue: May 2023

<b>Plant:</b>	Seattle, Washington
<b>Product:</b>	TerraFlow 90
<b>Manufactured:</b>	April 2023
<b>Mill Test Report Number:</b>	TerraFlow90_May2023

### ASTM C 1157 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Slag, %	---	90	Passing 325 Sieve (%)	---	93.9
			Autoclave expansion (%)	0.8	-0.02
			Compressive strength (MPa)		
			3 days	5.0 min	9.2
			7 days	11.0 min	15.3
			28 days	--	24.4

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of applicable Specifications for Type MH

**Seattle Plant**  
 5400 W. Marginal Way SW, Seattle, WA 98106  
 Phone: 206-937-8025

Certified By:

**Daniel Waldron - QC Laboratory Supervisor**

July 15, 2021