



materials

7

TerraFlow® Mill Test Report

Month of Issue: June 2023

Plant: **Product:** Manufactured: Mill Test Report Number:

Seattle, Washington **TerraFlow 75** May 2023 TerraFlow75_June2023

ASTM C 1157 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Slag, % Type IL, %		75 25	Passing 325 Sieve (%)		94.1
			Autoclave expansion (%)	0.8	-0.01
			Compressive strength (MPa)		
			3 days 7 days 28 days	5.0 min 11.0 min 	13.5 23.4 36.6

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of applicable Specifications for Type MH

Seattle Plant 5400 W. Marginal Way SW, Seattle, WA 98106 Phone: 206-937-8025

Certified By:

Robert J. Shoopen

Rob Shogren Technical Director

June 5, 2023