



# TerraFlow® Mill Test Report

Month of Issue: October 2023

Plant: Seattle, Washington  
Product: TerraFlow 90  
Manufactured: September 2023  
Mill Test Report Number: TerraFlow90\_October2023

## ASTM C 1157 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Slag, %	---	90	Passing 325 Sieve (%)	---	91.2
			Compressive strength (MPa)		
			3 days	5.0 min	9.7
			7 days	11.0 min	12.8
			28 days	--	23.3

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of applicable Specifications for Type MH

Seattle Plant  
5400 W. Marginal Way SW, Seattle, WA 98106  
Phone: 206-937-8025

Certified By:

Rob Shogren - Technical Director

October 2, 2023