



Mill Test Report

Month of Issue: December 2024

Plant: Seattle, Washington
Product: TerraFlow 90
Manufactured: November 2024
Mill Test Report Number: TerraFlow90_December2024

ASTM C 1157 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	Item	Spec limit	Test Result
Slag, %	---	90	Passing 325 Sieve (%)	---	96.2
Type IL, %	---	10			
			Compressive strength (MPa)		
			3 days	5.0 min	12.5
			7 days	11.0 min	19.0
			28 days	--	25.0

We certify that the above described cement, at the time of shipment, meets the chemical and physical requirements of applicable Specifications for Type MH

Seattle Plant
5400 W. Marginal Way SW, Seattle, WA 98106
Phone: 206-937-8025

Certified By:

Rob Shogren - Technical Director

December 5, 2024