

Cement Mill Test Report

Date of Issue: April 7, 2025

Plant: Product: Mill Test Report Number: Manufactured during the month of: Exshaw, AB Portland Cement Type III ESW_Type III 2025-03 March 2025

ASTM C 150-24 and AASHTO M 85-24 Standard Requirements

CHEMICAL ANALYSIS			PHYSICAL ANALYSIS		
Item	Spec limit	Test Result	ltem	Spec limit	Test Result
Rapid Method, X-Ray (XRF) ((C114)		Air content of mortar (%) (C185)	12 max	5
SiO ₂ (%)	·	19.2			
Al ₂ O ₃ (%)		4.0	Blaine Fineness (m²/kg) (C204)		472
Fe ₂ O ₃ (%)		3.4			
CaO (%)		61.6	Passing 45 μm (%) (C430)		99.2
MgO (%)	6.0 max	4.7	·		•••=
SO ₃ (%) **	3.5 max	3.4	Compressive strength (MPa, [psi]) (C	109)	
Loss on Ignition (%)	3.5 max	2.5	1 day	, 12.0 [1740] min	21.0 [3052]
Insoluble Residue (%)	1.5 max	0.4	3 days	24.0 [3480] min	33.3 [4823]
CO ₂ (%)		1.8	28 days (Previous Month's Result)	[0.100]	47.0 [6818]
Limestone (%)	5.0 max	4.3			
CaCO ₃ in Limestone (%)	70 min	96.0			
Inorganic Process Addition	5.0 max		Time of setting (minutes)		
(Lafarge Cement Kiln Dust)			Vicat Initial (C191)	45 - 375	83
Adjusted Potential Phase Composition (C150)			Mortar Bar Expansion (%) (C1038)	0.020 max	0.012
C ₃ S (%)		56			
C ₂ S (%)		12			
C ₃ A (%)	15 max	5			
C₄AF (%)		10			
ASTM C 150-24 and AASHTO	M 85-24 Optional C	Chemical Requiremen	ts:		
Na ₂ Oeq (%) Weekly Averages	: Week	1 0.57 Week	2 0.56 Week 3 0.58 Week	4 0.58	Max 0.60
** May exceed 3.0% SO3 maximum based We certify that the above d and physical requirements	escribed cement		nent, meets the chemical	Certified to NSF(ANS)/CAN 61	
ASTM C 150-24 & AASHTC	O M 85-24 STAND	ARD SPECIFICATIO	NS FOR TYPE III CEMENT; and		
ASTM C 150-24 & AASHTO	M 85-24 OPTION	IAL CHEMICAL REC	UIREMENTS FOR TYPE III LOW ALK	ALI CEMENT.	
Exceptions: C430 is excluded fr	om the scope of the	AASHTO accreditation		$1, \sum_{n}$	
Western Canada BU - Exs	shaw Plant		Certified By:	A L. YH	$\sqrt{1}$
P.O. Box 160, Highway 1A, Exsh	aw AB, T0L 2C0				<u></u>
Phone: 403-673-3815			7	John W Blair Quality Manager	



Cement Mill Test Report

Date of Issue: April 7, 2025

Plant: Product: Mill Test Report Number: Manufactured: Exshaw, AB Portland Cement Type III ESW_Type III 2025-03 March 2025

ASTM C 150-24 and AASHTO M 85-24 Standard Requirements

Additional Data

Item	Test Result			
	Limestone	Inorganic Process Addition		
		Lafarge Cement Kiln Dust		
Amount (%)	4.3			
SiO ₂ (%)	2.4	13.0		
Al ₂ O ₃ (%)	0.5	3.5		
Fe ₂ O ₃ (%)	0.3	1.8		
CaO (%)	48.8	46.0		
SO ₃ (%)	0.2	2.8		
CO ₂ (%)	42.3	n/a		

Base Cement Phase Composition

Item	Test Result	
C ₃ S (%)	59	
C ₂ S (%)	13	
C ₃ A (%)	5	
C ₄ AF (%)	11	

Specific Gravity (For Information Purposes Only)

3.15

We certify that the data above reflects the materials used in cement manufacture during the production period indicated.

Western Canada BU - Exshaw Plant P.O. Box 160, Highway 1A, Exshaw AB, T0L 2C0 Phone: 403-673-3815

Certified By: John W Blair

Quality Manager